



Bids

Estimate #17798 - Best

Description	Quantity	Price	Total
Sealcoat Clean the asphalt surface remove all debris treat oil spots with petro-seal and apply an industrial-grade asphalt emulsion sealer. 8,429sf	1	\$2,950.15	\$2,950.15
Crack Sealing Clean cracks of vegetation and debris. Pump a hot rubberized low tack sealer into cracks and voids using a Crafcro SuperShot 125 machine leaving 2" band over crack. Excludes alligator and parking stall areas unless specified. 200lf	1	\$250.00	\$250.00
Heavy Cleaning Scrub the area to remove moss dirt build up and debris.	1	\$350.00	\$350.00
Supplies / Shop Charge Standard fee for disposable/process items utilized in painting, crack sealing and seal coat application.	1	\$129.95	\$129.95
DISCLAIMER-GENERAL By accepting this estimate you are agreeing to the following: 1.Tax will be added to the final invoice at the current rate at time of project completion. 2. Guardian LLC reserves the right to Lien Project location at 30 days after completion for nonpayment. 3.Estimates are subject to change after 30 days.	1	\$0.00	\$0.00

Description	Quantity	Price	Total
Asphalt I/We hereby request Guardian LLC to furnish all labor and materials necessary to manufacture and install on the following premises listed above. Scope of work: Cut and remove damaged asphalt and roots next to bollards, 10x11 @ 110sf replace with Class B hot mix. 1.37 tons are required for this project at 2". If thickness is more than 2" then an extra material cost will apply at \$295.00 per ton. The customer will be notified before proceeding. Exclusions: (Unless specified otherwise) Prime coat aggregate Surveying Engineering Patching Traffic Control Inspection Testing Permits Performance or Warranty Bond.	1	\$1,850.00	\$1,850.00
Asphalt I/We hereby request Guardian LLC to furnish all labor and materials necessary to manufacture and install on the following premises listed above. Scope of work: Cut drive smooth and pave area next to drive at gate, 6x48 @ 288sf with Class B hot mix. 3.6 tons are required for this project at 2". If thickness is more than 2" then an extra material cost will apply at \$295.00 per ton. The customer will be notified before proceeding. Exclusions: (Unless specified otherwise) Prime coat aggregate Surveying Engineering Patching Traffic Control Inspection Testing Permits Performance or Warranty Bond.	1	\$3,240.32	\$3,240.32
Total:		\$8,770.42	

 Accept "Best" Bid

 View All Bids (/bids)

 Reject All Bids & Proposal